



110 Coolidge Avenue - Contributing

This is a one- and one-half story side-gabled Craftsman dwelling built ca. 1930. The house has a roof of asphalt shingles, an exterior brick chimney, a continuous brick foundation and an exterior of wood shingles. On the main (S) elevation is a full-width, shed roof porch with square, brick columns enclosed ca. 1950 with three-over-one-vertical light double hung wood sash windows and a brick exterior. The main entrance retains its original, three-vertical-light glass and wood door with an aluminum and glass storm door and flanking louvered wood shutters. Windows are original, three-over-one-vertical-light double hung wood sash with wood surrounds. At the eaves are knee brace brackets. On the rear façade is a ca. 1950, shed roof addition with an exterior of wood shingles and one-over-one double hung wood sash windows.



To the rear of the dwelling is an original, frame, one-bay garage with a gable front roof of asphalt shingles, an exterior of weatherboard siding and an original fifteen-wood panel overhead track door. Adjacent to the bay garage door is an original, pedestrian five-panel wood door.

- Contributing



115 Coolidge Avenue - Contributing

Located at 115 Coolidge Avenue is a two-story, brick, rectangular Craftsman style dwelling built ca. 1920. The house has a continuous poured concrete foundation, a gable roof of asphalt shingles, an exterior wall brick chimney and exterior of brick veneer. On the main (N) façade is a partial-width, gable roof porch with square brick columns and a solid brick railing with a concrete cap. The main entrance has an original, four-light and single wood panel Craftsman door. Windows are original, three-over-one-vertical-light double hung wood sash. The first floor's main façade has a five-over-one vertical light double hung wood sash window flanked by two-over-one double hung wood sash windows. On the east façade is a secondary entrance with an original glass and wood door. At the roofline of the east façade is a large gable roof dormer with paired, three-over-one-vertical-light double hung wood sash windows and knee brace brackets at the eaves. At the roof eaves are purlins, knee brace brackets and exposed eave rafters.



Located to the rear of the dwelling is an original, single-bay, brick garage with a gable roof of asphalt shingles and replacement metal panel overhead track garage door. - **Contributing**



116 Coolidge Avenue - Noncontributing

Located at 116 Coolidge Avenue is a one-story gabled ell Colonial Revival influenced dwelling built ca. 1955. The dwelling has an exterior of aluminum siding, a gable roof of asphalt shingles, a continuous concrete foundation and an interior concrete chimney. On the main (S) façade is an inset entry with a single square wood post, wood milled brackets, a concrete floor and steps and a wide wood cornice. The main entrance has a wood panel door concealed by an aluminum and screen storm door. Adjacent to the door is a projecting bay beneath the front gable which has a large two-over-two horizontal-light, double hung wood sash window flanked by two-over-two horizontal-light double hung windows with two-over-two double hung horizontal-light windows on the sides; all original. The remaining windows in the dwelling are original, two-over-two horizontal light double hung wood sash with simple wood surrounds and flanked by louvered wood shutters. On the gable field of the main façade is board and batten siding and a rectangular louvered metal attic vent.

Off the northeast corner is an original single-bay, frame garage with an exterior of aluminum siding, a front gable roof of asphalt shingles and a ca. 1980, metal panel overhead track door.
Noncontributing



119 Coolidge Avenue - Contributing

This is a two-story side-gabled Colonial Revival style dwelling built ca. 1920. The house has an exterior of weatherboard siding, a roof of asphalt shingles with gable returns, an exterior brick chimney and a continuous brick foundation. On the main (N) façade is a centrally sited entrance beneath a gable roof entry porch supported by Tuscan columns with an arched ceiling. The main entrance retains its original, four-light and four-wood panel door with original four-light glass and wood sidelights above which is an original wood sunburst panel. Windows are original, six-over-one double hung wood sash. Centrally located on the upper façade is a square, multi-light Craftsman-style leaded glass window.



Located to the rear of the dwelling is a ca. 1930, one-bay, frame garage with a gable roof of asphalt shingles with gable returns, an exterior of weatherboard siding and a ca. 1950, thirty-two wood panel overhead track door.

- Contributing



120 Coolidge Avenue - Contributing

This is a one and one-half story gabled ell Folk house with French Countryside influence, built ca. 1920. The house has a clipped gable roof of asphalt shingles. The projecting bay on the main (S) façade has an original, small inset porch on its east elevation which was remodeled in the late 20th century with the addition of a milled railing and frieze. The dwelling has an exterior of weatherboard siding and a continuous poured concrete foundation. Windows are original, eight-light wood casement design. On the west elevation are two, ca. 1980, large shed roof dormers. The dormers are a polygonal bay design with three, single-light fixed windows. Between the two dormers is a newly constructed large metal flue.



To the rear of the dwelling is an original, frame, one-bay garage with a clipped front gable roof of asphalt shingles, an exterior of vinyl siding, a pedestrian door with a canvas canopy adjacent to a ca. 1990 large overhead track metal door on the main facade.

- Contributing



123 Coolidge Avenue - Noncontributing

Located at 123 Coolidge Avenue is a two-story, frame, Colonial Revival style dwelling built ca. 1955. The dwelling has a gable roof of asphalt shingles, an exterior wall stone chimney, an exterior of weatherboard siding and a continuous concrete foundation. In the projecting bay on the first floor is an exterior of stone veneer. On the main (N) façade is a partial-width porch with round wood posts and an arched frieze. The east bay is recessed and has an integrated garage bay with an original, six-light glass and wood panel overhead track door. Windows are original eight-over-eight and six-over-six double hung wood sash with original storm windows. On the main façade the projecting bay is cantilevered on the upper facade and in the gable field is an elliptical attic window. Adjacent to the cantilevered bay on the upper façade roofline is a gable roof dormer with an original six-over-six double hung wood sash window on the east façade and two, gable roof wall dormers with six-over-six double hung wood sash windows on the west side.



124 Coolidge Avenue - Contributing

Located at 124 Coolidge Avenue is a 1-1/2 story, frame, gable front Folk dwelling constructed with Craftsman influences ca. 1915. The house has a clipped gable roof of asphalt shingles, a continuous foundation of rock-faced, hollow core concrete block, an interior brick chimney and an exterior of vinyl siding. On the main (S) façade is a full-width, hipped roof porch with original, tapered wood columns and a solid wood railing covered with aluminum siding. The main entrance retains its original, eight-light and wood panel Craftsman style door. Windows are original, one-over-one rectangular double hung wood sash with one-over-one storm windows. On the lower façade of the main façade is a bay window with three, one-over-one wood double hung sash windows. At the roofline on the east façade is a large, ca. 1970, shed roof dormer with metal sash windows.



To the rear of the dwelling is an original, frame, single-bay garage with an exterior of shiplap siding, a hipped roof of asphalt shingles and an original, twelve-light glass and six-vertical wood panel overhead track door.

- Contributing



128 Coolidge Avenue – Contributing (ARC Case 01-24)

This is a one and one-half story side-gabled Craftsman dwelling built ca. 1930. The dwelling has a continuous brick foundation, a roof of asphalt shingles, a central interior brick chimney and an exterior of narrow weatherboard siding. On the main (S) elevation is a partial-width, inset porch with square wood posts. A set of four wood steps framed by a wood baluster railing lead to the porch's wood floor. The main entrance retains its original nine-light glass and wood door. Windows are original, one-over-one double hung wood sash. Also, on the main elevation is a gable roof dormer with an exterior of weatherboard siding, knee brace brackets, exposed roof rafters and a triple set of one-over-one double hung wood sash windows. Knee brace brackets are also located in the gable fields of the east and west elevations of the dwelling. At the rear of the dwelling is a single-story, gable roof addition built ca. 1970 with an entry on the east façade.



To the rear of the dwelling is an original, two-bay, frame, garage with a hipped roof of asphalt shingles, exposed roof rafters and a weatherboard exterior. On the south elevation are two, four-light and sixteen-panel glass and wood overhead track doors. - **Contributing**



129 Coolidge Avenue - Contributing

This is a ca. 1925, two-story Dutch Colonial-style dwelling with a side-gabled gambrel roof of asphalt shingles, a continuous brick foundation, an exterior brick chimney and an exterior of aluminum siding. The house retains its original entrance on the main (N) elevation with a six-panel wood door flanked by four-light glass and wood sidelights. Above the door is an elliptical sunburst pattern transom. The entrance leads to a gable roof entry porch with Tuscan columns and a large exaggerated arched ceiling. Windows are original ten-over-one and eight-over-one double hung wood sash design. On the west elevation of the dwelling is an original porte-cochere with a flat roof supported by Tuscan columns, exposed roof rafters and a wood lattice trellis. Dividing the upper and lower facades is a shed roof beltcourse.

Off the southwest corner of the dwelling is an original, stone-faced concrete block, one-bay garage with a hipped roof of asphalt shingles and a ca. 1995, thirty-two metal panel overhead track door. - **Contributing**





132 Coolidge Avenue - Contributing

Located at 132 Coolidge Avenue is a one-story, frame, gabled ell Tudor Revival-style dwelling built ca. 1930. The house has a roof of asphalt shingles, a poured concrete foundation, an exterior wall brick chimney and an exterior of wood shingles. On the main (S) façade is a steeply-pitched gable roof projecting vestibule entry that contains an original, arched entrance. This entrance has an arched Tudor-style wood door with an original, arched eight-light storm wood door flanked by an original six-light wood casement window. The main façade exterior wall brick chimney is of tan colored wired brick with concrete inset panels. Windows are original, six-over-six rectangular double hung wood sash with wood cornice surrounds. At the eaves are gable returns. In the gable field is a fixed, fanlight attic window on the main façade. The side façade gable fields have small, six-over-six double hung wood sash attic windows.



Off the northeast corner of the dwelling is an original, one-bay, frame garage with a gable roof of asphalt shingles, an exterior of shiplap siding, and its original, twenty-four wood panel overhead track door.

- Contributing



135 Coolidge Avenue - Noncontributing

Two-story side-gabled brick veneer dwelling built ca. 1962.



136 Coolidge Avenue - Contributing

This is a one- and one-half story side-gabled Craftsman dwelling built ca. 1925. The house has a continuous brick and poured concrete foundation, a roof of asphalt shingles, an interior brick chimney and exterior of aluminum siding. On the main (S) façade is a partial-width, inset porch with square wood posts and a closed wood railing covered with aluminum siding. The main entrance retains its original, three-vertical-light glass and wood door with an aluminum and glass storm door. Windows are original, four-over-one-vertical-light double hung wood sash. On the east façade is a projecting shed roof bay with three, three-over-one-vertical-light double hung wood sash windows. At the roofline of the main façade is a gable roof dormer with a triple set of three-over-one-vertical-light double hung wood sash windows.



At the rear of the dwelling is an original, two-bay, frame garage with original weatherboard siding, a hipped roof of asphalt shingles and two, original, sixteen-wood-panel overhead track doors. At the roofline is a small, hipped roof dormer with paired single-light windows currently boarded over with wood.
- **Contributing**



141 Coolidge Avenue - Contributing

Located at 141 Coolidge Avenue is a one-and one-half story Folk dwelling built ca. 1910 with a gable front main section and a one-story lateral wing on the east façade. The house has a gable roof of asphalt shingles, an interior brick chimney, an added exterior wall brick chimney, an exterior of aluminum siding and a rock-faced concrete block continuous foundation. On the main (N) façade is a hipped roof porch with ca. 1970, square wood columns and a square wood baluster railing. The main entrance has a ca. 1970, multi-light glass and wood door. On the west façade is a secondary entrance with a glass and wood door and a ca. 1970, shed roof canopy supported by square wood posts and railing. Windows are original one-over-one and two-over-two vertical-light double hung wood sash and replacement, ca. 1990, one over-one double hung aluminum sash.

To the rear of the dwelling is a ca. 1970 frame garage. – **Noncontributing**



200 Coolidge Avenue - Contributing

This is a 1934 gable front Folk church building that has been converted into a single-family residence. The building has a stone-faced concrete block foundation, an interior brick chimney, an exterior of weatherboard siding and a gable roof of asphalt shingles. The building was built in a gable front design with a central square bell tower situated at the juncture of the entry vestibule with the main section of the building. On the main (S) elevation is a gable entry vestibule with paired four-panel wood doors. The entrance is set within a simple arched wood frame with a broken pediment. Above the doors is an original four-light glass and wood transom and a circular canvas and aluminum canopy. In the gable fields and on the exterior of the bell tower is an exterior of board and batten siding. Windows are original two-over-two double hung wood sash eight-light glass and wood fixed windows on the main elevation with simple wood cornices. On the basement level are three-light fixed glass and wood windows. On the rear elevation is an original wing with a double gable roof, an exterior of weatherboard siding and four-over-four double hung wood sash windows.

To the rear of the building is a frame gable roof garage built ca. 1990. – **Noncontributing**



201 Coolidge Avenue - Noncontributing

This is a ca. 1960 Rectangular brick veneer Ranch style dwelling.



205 Coolidge Avenue - Contributing

Located at 205 Coolidge Avenue is a small, frame, side-gabled one-story Folk cottage built ca. 1930. The cottage has a roof of asphalt shingles, an interior brick chimney, a continuous stone-faced concrete block foundation and an exterior of synthetic siding. The full-width, inset porch on the main (N) façade has been enclosed with synthetic siding and sliding track vinyl clad windows with flanking vinyl shutters. The main entrance has an original, three-horizontal-light and three-horizontal wood panel door which lead to wood steps with PVC railings. Windows are single-light casement design and one-over-one double hung wood sash.

Off the southwest corner of the dwelling is an original, frame garage with a front gable roof of asphalt shingles, horizontal board siding and vertical board hinged double doors. - **Contributing**





206 Coolidge Avenue - Contributing

Located at 206 Coolidge Avenue is a one-story, frame, gabled ell Tudor Revival dwelling built ca. 1930. The house has a continuous foundation of rock-faced, hollow core concrete block, a gable roof of asphalt shingles and an exterior of wood shingles. On the main (S) façade is an inset entry porch on the east façade of a gabled projecting bay. This entry porch has two, arched openings and a column covered with wood shingles. The main entrance retains its original arched, four-panel wood door set within an arched surround. Windows are original, six-over-one rectangular double hung wood sash with simple wood surrounds. On either side of the chimney are stained glass windows. Beneath the windows on the main façade are wood flower boxes. On the rear façade is a ca. 1950, shed roof addition.



Located to the rear of the dwelling is an original, two-bay, frame garage with a front gable roof of asphalt shingles, an exterior of shiplap siding and original overhead track wood panel garage doors. Located in the gable field are natural birdhouses.

- Contributing



209 Coolidge Avenue - Noncontributing

This is a ca. 1960, frame, gabled ell Ranch style dwelling.



212 Coolidge Avenue - Contributing

This is a two- and one-half-story, gabled ell plan, Folk dwelling built ca. 1910. The house has a gable roof of asphalt shingles, a central interior brick chimney, an exterior brick chimney and an exterior of weatherboard siding. The continuous foundation has a stucco-covered exterior. On the main (S) façade is a one-story, hipped roof porch set within the ell and enclosed with two-over-two double hung sash windows and an exterior of weatherboard siding. The main entrance retains an original, single-light glass and wood door. Windows are original, two-over-two and one-over-one double hung wood sash with simple wood cornice surrounds and flanking wood shutters on the main façade. On the dwelling's east elevation is a small, two-story, flat roof addition built ca. 1955. An entrance to this addition on the south elevation has an eight-light glass and wood door.



To the rear of the dwelling is a ca. 1950 two-bay, one- and one-half-story, frame garage with a pedestrian entrance on the south elevation. The garage has a gambrel roof of asphalt shingles and two, ca. 1980, overhead track metal panel doors. – **Noncontributing**



215 Coolidge Avenue - Contributing

Located at 215 Coolidge Avenue is a one- and one-half story, gabled ell Craftsman dwelling built ca. 1930. The house has a roof of asphalt shingles, a continuous stone-faced concrete foundation, an exterior brick chimney, and a wood shingle exterior. On the main (N) elevation is a small inset entry bay with a wood shingle-sided square post and a closed railing with a wood cap. Wood baluster railings line the wood steps to the fieldstone walkway. The main entrance retains its original, Craftsman-style, four-light glass and wood door. Windows are replacement, double hung vinyl sash with false muntin bars for a three-over-one-vertical-light effect. Windows are grouped in pairs, triples and sets of four. The house has exposed roof rafters at the eaves. At the roofline of the main façade is a gabled roof dormer with a triple set of windows and exposed roof rafters.

To the rear of the dwelling is an original, two-bay garage with a clipped gable roof of asphalt shingles, a weatherboard exterior and two, ca. 1990, overhead track metal panel doors. - **Contributing**





218 Coolidge Avenue - Noncontributing

Located at 218 Coolidge Avenue is a one-story, frame, gabled ell Ranch style dwelling built ca. 1955. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles, an interior central brick chimney and a continuous brick foundation. On the main (S) façade is an inset porch with a geometrical wood design support on a brick pier. The main entrance has a multi-light glass and wood door with a wood and glass storm door. Windows are two-over-two horizontal sash double hung metal sash. On the main façade is a large picture window with a flanking two-over-two double hung metal sash window on its west facade. The dwelling is considered non-contributing at this time because of its age and should be re-accessed upon arriving at fifty-years of age.

Off the northwest corner is a ca. 1965, single bay, brick garage with a metal overhead track door. **Noncontributing**



221 Coolidge Avenue - Contributing

Located at 221 West Coolidge Avenue is a one- and one-half story, frame, side-gabled Craftsman dwelling built ca. 1925. The dwelling has a roof of asphalt shingles, an exterior of aluminum siding and a continuous foundation of rock-faced concrete blocks. On the main (N) façade is a full-width porch which was enclosed with aluminum jalousie windows and aluminum siding ca. 1970. The main entrance has a ca. 1970, eight-light glass and wood Craftsman-style door flanked by single-light glass and wood sidelights. Windows are original, six-over-one double hung wood sash. In the eaves are purlins and exposed eave roof rafters. At the roofline on the main façade is a gabled roof dormer with paired, three-over-one double hung wood sash windows, exposed roof rafter ends and purlins.



Located to the rear of the dwelling is an original, two-bay, side gable roof garage with a side gable roof of asphalt shingle, an exterior of board and batten siding and two, replacement overhead track metal panel garage doors. - **Contributing**



225 Coolidge Avenue – Contributing

This is a one-story, frame, gable front Craftsman dwelling built ca. 1935 and remodeled ca. 1985. The dwelling has a front gable roof of asphalt shingles, an original interior brick chimney, an exterior brick chimney and an exterior of aluminum siding. On the main (S) elevation is a partial-width, gable roof, porch with a patio extension supported by square wood posts and slightly arched solid wood openings. The dwelling retains its original, four-light Craftsman-style glass and wood door with an aluminum and screen door. Windows are replacement ca. 1985, single-light casement vinyl clad designs. Both the porch and dwelling have exaggerated knee brace brackets at the eaves. On the east façade is a gable roof projecting bay with a single window and knee brace brackets. On the rear façade, a large rear addition was constructed ca. 1985.



Located off the southwest corner of the dwelling is a ca. 1980, frame garage with an exterior of vinyl siding, a horizontal metal panel overhead track door and a front gable roof of asphalt shingles. – **Noncontributing**





226 Coolidge Avenue - Noncontributing

This is a two- and one-half- story, frame, gabled ell Queen Anne-influenced dwelling built ca. 1995. To the rear of the dwelling is a ca. 1990 frame garage. **Noncontributing**



227 Coolidge Avenue - Noncontributing

This is a ca. 1930 frame dwelling drastically remodeled ca. 1970 with a new roofline, a large rear addition and porch. The dwelling retains its original wood shingle exterior and windows. Located to the rear of the dwelling is a remodeled frame garage. **Noncontributing**



230 Coolidge Avenue - Contributing

This is a one- and one-half-story, frame side-gabled Folk dwelling built ca. 1930. The dwelling has a steeply pitched roof of asphalt shingles, an exterior of weatherboard siding, an exterior brick chimney, and a stucco-covered, continuous foundation. The main entrance is centrally located on the south elevation and has a gabled entry porch with Tuscan columns and an arched ceiling. A wooden railing lines the porch and wood steps. The entrance has an original, three-vertical light glass and wood paneled door. On the east elevation is an original one-story wing. Windows are original three-over-one-vertical-light double hung wood sash. On the rear elevation, is an original, one-story enclosed porch with eight-light glass and wood windows. A ca. 2003, new frame deck is also located off the rear elevation.



To the rear of the dwelling is an original, two-bay, frame garage with a side gable roof of asphalt shingles, an exterior of weatherboard siding and two, ca. 1990, overhead track metal doors. - **Contributing**



231 Coolidge Avenue - Noncontributing

This is a ca. 1930 frame gable front dwelling extensively remodeled ca. 1990 with vinyl siding, an added porch deck and replacement doors and windows. Located to the rear of the dwelling is a remodeled frame garage. **Noncontributing**



234 Coolidge Avenue - Noncontributing

Located at 234 West Coolidge Avenue is a one- and one-half story frame, side-gabled Neo-Cape Cod dwelling built ca. 1930. The house has a rock-faced concrete block foundation, a side gable roof of asphalt shingles, an exterior wall brick chimney and an exterior of weatherboard siding. The main (S) façade has a gable roof canopy supported by knee brace brackets and ca. 1970 wrought iron posts. The entrance has a six-panel wood door flanked by original, four-light glass and wood sidelights and above the door is a swan's neck pediment and urn. Windows are ca. 1990, six-over-one double hung vinyl sash. At the roofline on the main facade are two, gable roof dormers with ca. 1990 vinyl sash windows. On the rear façade is a large shed roof dormer. Beneath the windows on the main façade are wood flower boxes supported by wood brackets. On the east façade is an original, hipped roof addition with a garden window on its east facade and triple sets of windows to possibly form a sunroom. To the east of the dwelling is an original concrete ribbon driveway.



At the rear of the dwelling is a ca. 1970, two-bay garage with a side gable roof of asphalt shingles, an exterior of vinyl siding and two, ten-wood panel overhead track doors.
- Noncontributing



235 Coolidge Avenue - Noncontributing

Located at 235 Coolidge Avenue is a ca. 1970 gabled ell brick veneer dwelling.



238 Coolidge Avenue - Contributing

Located at 238 Coolidge Avenue is a two-story, frame, gable front Folk dwelling built ca. 1880. The house has a front gable roof of asphalt shingles, an interior brick chimney, a continuous stone foundation and an exterior of masonite siding with a permastone skirt wall on the main façade. The main (S) façade has a gable roof canopy over the main entrance supported by wood brackets, concrete stairs and a wrought iron railing. The main entrance has a ca. 1960, three-rectangular-light diagonal line glass and wood door. Windows were replaced ca. 1960 which included an installation of a large central single-light fixed picture window with flanking two-over-two double hung wood sash windows on the main façade's first floor. This dwelling was extensively altered ca. 1960 and has lost most of its historic fabric and detailing. On the rear façade is a ca. 1960, single-story, gable roof addition with a lateral wing that attaches a ca. 1960, single-bay garage with a twelve-wood panel and four-light overhead track door and a single-light and wood panel pedestrian door. An entry on the west façade has a shed roof porch supported by a single milled wood post. .



239 Coolidge Avenue – Contributing

This is a two- and one-half story, side-gable with wings, Colonial Revival dwelling built ca. 1930. The house has a side gable roof of multi-colored slate shingles, a continuous brick foundation, a brick exterior and two exterior end brick chimneys. The main entrance is centrally located on the north elevation and has an original wood paneled door flanked by original four-light glass and wood panel sidelights. The entrance leads to a small entry porch with an arched roof supported by square wood posts. Windows are original six-over-one double hung wood sash with brick sills. Upper floor windows have wood plank shutters with three-leaf shamrock cutouts and are set within a shed roof wall dormer. On both the east and west elevations are one-story flat roof wings. At the basement level beneath the eastern wing is a garage bay with an original six-light and eighteen-panel wood and glass garage door. Fanlight attic windows flank the chimney at the attic level on both the east and west elevations. The house has a belt course of soldier course brick above the first floor windows. Poured concrete walls extend from garage bay along driveway.



244 Coolidge Avenue - Noncontributing

This is a two-story, Dutch Colonial Revival style dwelling constructed ca. 1980. To its rear is a ca. 1980 frame, front gable roof single bay garage. **Noncontributing**



247 Coolidge Avenue - Noncontributing

Located at 247 Coolidge Avenue is a one-story asymmetrical Minimal Traditional-style dwelling built ca. 1945. The dwelling has a continuous concrete foundation, an interior brick chimney, an exterior of aluminum siding and a side gable roof of asphalt shingles. Located on the main (N) elevation is a projecting gable with an inset porch on the northwest corner. The entrances have been replaced with ca. 1980 glass and wood doors. Windows are original six-over-six double hung wood sash. Also on the main elevation is a twenty-light fixed glass and wood picture window with flanking six-over-nine double hung wood sash windows. The breezeway between the dwelling and garage on the west elevation was enclosed ca. 1960 with two-over-two horizontal-light double hung wood sash windows and a single-light glass and wood door. The attached single-bay, frame garage has a front gable roof of asphalt shingles, an exterior of aluminum siding and an ca. 1990, overhead track metal paneled door.



250 Coolidge Avenue - Contributing (ARC Case 01-18)

This is a two-story, frame, gabled ell Folk dwelling built ca. 1900. The house has a gable roof of wood shingles, a central interior brick chimney, an exterior of weatherboard siding, and a foundation of continuous concrete block. On the main (S) façade is a wraparound, hipped roof porch with square wood posts, a wood floor, a wood railing with simple square wood balusters and wood corner brackets with a circular design. The main entrance has a four-panel wood door with an original exterior wood screen door. Windows are original, one-over-one double hung rectangular wood sash with simple wood cornice surrounds. The rear elevation has a small, one-story gable wing with a small stoop on the north elevation. Both the entrance into the one-story wing and the entrance on the rear elevation on the main section of the dwelling have ca. 1990, nine-light glass and wood doors.



To the rear of the dwelling is a ca. 1950, hipped roof, frame garage with an exterior of aluminum siding, an original five-wood panel pedestrian door and an original sixteen-wood panel overhead track door.

- Noncontributing